PV102 Day 8 Morning Quiz

10 questions | 15 minutes | Independent work

PV102 | CTS Day 24 | Morning Quiz - Student
Test, document, and hand off what the system actually does. | Thursday, August 13, 2026

Directions: Answer from your current knowledge. For written responses, use complete technical statements. If unsure, state the safe next action rather than guessing.

1. Commissioning means:

- A. Verifying a system before/while placing it into service
- B. Buying the biggest inverter
- C. Painting a roof
- D. Guessing until it works

2. Before continuity testing, the circuit must be:

- A. De-energized and verified
- B. Fully energized
- C. Connected to utility
- D. Under maximum load

3. Polarity checks help prevent:

- A. Reverse connection damage or unsafe operation
- B. Too much sunlight
- C. Roof leaks only
- D. Bad handwriting

4. A professional handoff should include:

- A. Results, changes, unknowns, and next actions
- B. Only “it works”
- C. No measurements
- D. Guesswork

5. Good troubleshooting starts by:

- A. Defining the symptom and boundary
- B. Replacing random parts
- C. Blaming the battery immediately
- D. Skipping measurements

6. A 12 V battery reads 0 V at the load terminals. Name one possible boundary to check.

_____

_____

7. Why should failed tests be documented instead of hidden?

_____

_____

8. What should happen if a measurement does not make sense?

_____

_____

9. Name one item that belongs in a final PV102 handoff package.

_____

_____

10. Write the Day 8 rule in your own words.

_____

_____