RCS07 | Instructor Guide

CTS Cohort 6 | CTS Day 15 | 2026-07-29 | 10:00 AM-3:00 PM | 6 students

Integrated Wall Build: Correct, Complete, Prove

Core rule: A professional does not guess. A professional checks, protects, and verifies.

Big idea: Integration means every system fits, remains inspectable, and can be explained with evidence - not merely that the wall looks finished.

Architecture of the day

Time	Instructor move
10:00-10:15	Arrival, PPE, retrieval warm-up
10:15-10:30	Morning quiz
10:30-10:50	Quiz review and whole-wall QC frame
10:50-11:20	Subsystem and whole-wall inspection model
11:20-12:00	Punch-list and acceptance-criteria practice
12:00-12:30	Handoff evidence model and rework release
12:30-1:00	Lunch and controlled reset
1:00-2:25	Approved rework and capstone completion lab
2:25-2:45	Retest, whole-wall QC, handoff practice, cleanup
2:45-3:00	Exit ticket and final-practical preview

Learning targets

- Complete remaining capstone framing, electrical, and drywall work
- Run a subsystem and whole-wall QC inspection
- Diagnose and correct one documented defect
- Prepare a professional handoff package

Materials and setup

- Six capstone walls and current subsystem drawings
- Whole-wall QC checklists, punch-list forms, and acceptance criteria
- Task-specific hand tools and isolated electrical test equipment under prior controls
- Labels, evidence file-name plan, and approved cameras/devices
- Rework-zone barriers and cleanup materials
- Handoff rubric and 60-second timer

Instructor talking points

- Define system-level versus whole-project inspection.
- Model a punch list that names location, expected condition, observed condition, corrective action, and verification.
- Review all energy boundaries before students reopen device boxes or change wiring.
- Demonstrate evidence photos: overall, detail, test setup, and corrected result.
- Explain that honest documentation includes unresolved items rather than hiding them.

Whiteboard plan

1. Expected condition
2. Observed condition
3. Punch item owner
4. Correction
5. Retest/evidence
6. Ready for handoff?

Lab facilitation

Students complete their individual capstone walls, inspect framing dimensions, window opening, two outlets, switch/light path, drywall fit, fasteners, labeling, and evidence. Each student corrects at least one documented punch-list item and prepares a handoff.

Lab sequence

7. Pre-task plan
8. Energy-state verification
9. Whole-wall baseline inspection
10. Create punch list
11. Prioritize safety/functional defects
12. Complete approved work
13. Subsystem QC
14. Whole-wall QC
15. Correct one documented issue
16. Retest/reinspect
17. Capture evidence
18. Practice handoff
19. Reset

Safety boundaries

- Reapply the specific tool and energy controls for each task
- No energized student work

- Instructor approval before reopening covered or terminated systems
- Keep rework zones isolated
- Stop when a correction would create a new hazard or exceed training scope

Evidence targets

- Pre-task plan
- Whole-wall QC checklist
- Punch list
- Before/correction/after evidence set
- Draft handoff

Quiz answer key

1. What is a punch list? A documented list of incomplete, defective, or unverified items requiring action.

2. What should a useful punch item include? Location, expected condition, observed condition, owner/action, and verification result.

3. What is rework? Work performed to correct a nonconforming result.

4. What is traceability? The ability to connect a result to its process, inspection, evidence, and responsible action.

5. Why inspect subsystems before the whole wall? It isolates problems and confirms each system before integration.

6. What energy rule remains active during correction? No energized student work; isolate and verify before electrical work.

7. What four photo types support strong evidence? Overall, detail, test setup, and corrected result.

8. Should unresolved items be hidden during handoff? No; they must be clearly documented.

9. What proves a correction worked? A defined retest or reinspection with recorded evidence.

10. When is a wall ready for handoff? When acceptance criteria are met or remaining exceptions are explicitly documented and approved.

Exit-ticket look-fors

- Name your highest-priority punch item
- Describe the correction
- State the retest evidence
- Name any unresolved item honestly

Google Classroom post

RCS Day 7 - Integrated Wall Build: Correct, Complete, Prove

Today we focused on integration means every system fits, remains inspectable, and can be explained with evidence - not merely that the wall looks finished. Students completed guided instruction, hands-on capstone work, verification, evidence capture, and cleanup. Submit your worksheet, lab evidence, and exit ticket before leaving.

Source and safety references

- **Canonical RCS skeleton:** /CANONICAL/00_INBOX/Downloads/rcs_curriculum_plan.md
- **Cohort 6 RCS01 source:** /CANONICAL/02_PROJECTS/CTS_Cohort_06/03_DAILY/D09_RCS01_2026-07-20/Source/lesson.md
- **OSHA PPE:** https://www.osha.gov/personal-protective-equipment/construction
- **OSHA eye and face protection:** https://www.osha.gov/laws-regs/regulations/standardnumber/1926/1926.102
- **OSHA circuit lockout/tagging:** https://www.osha.gov/laws-regs/regulations/standardnumber/1926/1926.417
- **Oregon electrical codes:** https://www.oregon.gov/bcd/codes-stand/pages/electrical.aspx
- **Oregon permits:** https://www.oregon.gov/bcd/lbdd/pages/oregon-permits.aspx

RCS07 | Morning Quiz - Answer Key

CTS Cohort 6 | CTS Day 15 | 2026-07-29 | 10:00 AM-3:00 PM | 6 students

Integrated Wall Build: Correct, Complete, Prove

1. What is a punch list?

A documented list of incomplete, defective, or unverified items requiring action.

2. What should a useful punch item include?

Location, expected condition, observed condition, owner/action, and verification result.

3. What is rework?

Work performed to correct a nonconforming result.

4. What is traceability?

The ability to connect a result to its process, inspection, evidence, and responsible action.

5. Why inspect subsystems before the whole wall?

It isolates problems and confirms each system before integration.

6. What energy rule remains active during correction?

No energized student work; isolate and verify before electrical work.

7. What four photo types support strong evidence?

Overall, detail, test setup, and corrected result.

8. Should unresolved items be hidden during handoff?

No; they must be clearly documented.

9. What proves a correction worked?

A defined retest or reinspection with recorded evidence.

10. When is a wall ready for handoff?

When acceptance criteria are met or remaining exceptions are explicitly documented and approved.

Scoring guidance

One point per item. Accept technically equivalent wording. Use errors to reteach before lab release. Safety-boundary errors must be corrected explicitly before the student begins the related task.

RCS07 | Student Packet

CTS Cohort 6 | CTS Day 15 | 2026-07-29 | 10:00 AM-3:00 PM | 6 students

Integrated Wall Build: Correct, Complete, Prove

Core rule: A professional does not guess. A professional checks, protects, and verifies.

Big idea: Integration means every system fits, remains inspectable, and can be explained with evidence - not merely that the wall looks finished.

Learning targets

- Complete remaining capstone framing, electrical, and drywall work
- Run a subsystem and whole-wall QC inspection
- Diagnose and correct one documented defect
- Prepare a professional handoff package

Today's run

10:00-10:15 | Arrival, PPE, retrieval warm-up

10:15-10:30 | Morning quiz

10:30-10:50 | Quiz review and whole-wall QC frame

10:50-11:20 | Subsystem and whole-wall inspection model

11:20-12:00 | Punch-list and acceptance-criteria practice

12:00-12:30 | Handoff evidence model and rework release

12:30-1:00 | Lunch and controlled reset

1:00-2:25 | Approved rework and capstone completion lab

2:25-2:45 | Retest, whole-wall QC, handoff practice, cleanup

2:45-3:00 | Exit ticket and final-practical preview

Key words

integration | punch list | quality control | nonconformance | rework | handoff | evidence | acceptance criteria | traceability | reset

Guided worksheet

1. Complete the whole-wall QC checklist.

_____

_____

2. Create a numbered punch list.

_____

_____

3. Record one defect and its evidence.

_____

_____

4. Record the correction and retest.

_____

_____

5. Draft a 60-second handoff explanation.

_____

_____

Afternoon lab mission

Students complete their individual capstone walls, inspect framing dimensions, window opening, two outlets, switch/light path, drywall fit, fasteners, labeling, and evidence. Each student corrects at least one documented punch-list item and prepares a handoff.

Safety boundary

- Reapply the specific tool and energy controls for each task
- No energized student work
- Instructor approval before reopening covered or terminated systems
- Keep rework zones isolated
- Stop when a correction would create a new hazard or exceed training scope

Build / test sequence

[ ] Pre-task plan

[ ] Energy-state verification

[ ] Whole-wall baseline inspection

[ ] Create punch list

[ ] Prioritize safety/functional defects

[ ] Complete approved work

[ ] Subsystem QC

[ ] Whole-wall QC

[ ] Correct one documented issue

[ ] Retest/reinspect

[ ] Capture evidence

[ ] Practice handoff

[ ] Reset

Evidence record

[ ] Pre-task plan: _____

[ ] Whole-wall QC checklist: _____

[ ] Punch list: _____

[ ] Before/correction/after evidence set: _____

[ ] Draft handoff: _____

Reflection and exit ticket

Name your highest-priority punch item

_____

_____

Describe the correction

_____

_____

State the retest evidence

_____

_____

Name any unresolved item honestly

_____

_____

Instructor verification

Status: [ ] Approved [ ] Correct and recheck [ ] Needs follow-up

Instructor initials: _____ Date/time: _____

RCS07 | Morning Quiz

CTS Cohort 6 | CTS Day 15 | 2026-07-29 | 10:00 AM-3:00 PM | 6 students

Integrated Wall Build: Correct, Complete, Prove

Name: _____ Date: _____

Answer from your own understanding. This is a teaching check, not a trap.

1. What is a punch list?

_____

_____

2. What should a useful punch item include?

_____

_____

3. What is rework?

_____

_____

4. What is traceability?

_____

_____

5. Why inspect subsystems before the whole wall?

_____

_____

6. What energy rule remains active during correction?

_____

_____

7. What four photo types support strong evidence?

_____

_____

8. Should unresolved items be hidden during handoff?

_____

_____

9. What proves a correction worked?

_____

_____

10. When is a wall ready for handoff?

_____

_____