RCS06 | Student Packet

CTS Cohort 6 | CTS Day 14 | 2026-07-28 | 10:00 AM-3:00 PM | 6 students

Drywall Installation and Finish Readiness

Core rule: A professional does not guess. A professional checks, protects, and verifies.

Big idea: Finish quality is built through planning: inspect rough-in, measure openings, support the board, fasten correctly, control dust, and protect hidden systems.

Learning targets

- Complete a pre-cover inspection of framing and rough-in
- Measure and cut a 4-foot by 3-foot drywall panel
- Fit the panel around the window and device boxes
- Fasten and prepare the surface for finishing

Today's run

10:00-10:15 | Arrival, PPE, retrieval warm-up

10:15-10:30 | Morning quiz

10:30-10:50 | Quiz review and pre-cover misconception check

10:50-11:20 | Pre-cover inspection and opening-layout model

11:20-12:00 | Score/snap, cutout, and panel-handling demonstration

12:00-12:30 | Fastener QC, dust-control plan, and lab release

12:30-1:00 | Lunch and controlled reset

1:00-2:25 | Individual drywall fit and fastening lab

2:25-2:45 | Finish-readiness inspection, evidence, cleanup

2:45-3:00 | Exit ticket and Day 7 preview

Key words

gypsum board | factory edge | butt joint | score and snap | fastener dimple | overdriven | joint compound | tape | pre-cover inspection | dust control

Guided worksheet

1. Complete the pre-cover checklist.

_____

_____

2. Record the panel and opening measurements.

_____

_____

3. Sketch the box/window cutout reference points.

_____

_____

4. Classify three fastener examples: high, correct, overdriven.

_____

_____

5. Write the dust-control and cleanup plan.

_____

_____

Afternoon lab mission

Each student measures, cuts, fits, and fastens drywall over the 4-foot by 3-foot capstone board while protecting the window opening and electrical training boxes. Students perform a finish-readiness inspection and document corrections.

Safety boundary

- Eye protection during cutting
- Use dust controls and ventilation appropriate to the product/task
- Follow SDS and instructor PPE direction
- Support panels and use team handling when needed
- Keep blades retracted when not in use
- No covering until instructor signs pre-cover inspection

Build / test sequence

[ ] PPE and pre-cover inspection

[ ] Photograph rough-in

[ ] Measure panel/openings

[ ] Mark and partner-verify

[ ] Instructor cut approval

[ ] Score and snap/cut openings

[ ] Dry-fit

[ ] Fasten from supported center outward

[ ] Inspect fasteners and edges

[ ] Demonstrate tape/compound on sample

[ ] Dust-controlled cleanup

[ ] Document and reset

Evidence record

[ ] Pre-cover checklist: _____

[ ] Measurement/cutout worksheet: _____

[ ] Fitted panel photo: _____

[ ] Fastener QC record: _____

[ ] Finish-readiness inspection: _____

Reflection and exit ticket

Name one pre-cover check

_____

_____

Describe a correct fastener

_____

_____

State the dust-control plan

_____

_____

Name one correction made before approval

_____

_____

Instructor verification

Status: [ ] Approved [ ] Correct and recheck [ ] Needs follow-up

Instructor initials: _____ Date/time: _____

RCS06 | Morning Quiz

CTS Cohort 6 | CTS Day 14 | 2026-07-28 | 10:00 AM-3:00 PM | 6 students

Drywall Installation and Finish Readiness

Name: _____ Date: _____

Answer from your own understanding. This is a teaching check, not a trap.

1. Why inspect before covering the wall?

_____

_____

2. What is score and snap?

_____

_____

3. What is an overdriven fastener?

_____

_____

4. Why measure an opening from two reference edges?

_____

_____

5. What must protect workers during dusty tasks?

_____

_____

6. May drywall cover an unapproved rough-in?

_____

_____

7. What should a correct fastener do?

_____

_____

8. Why dry-fit before fastening?

_____

_____

9. What is finish readiness?

_____

_____

10. What professional habit applies to cutouts?

_____

_____