RCS08 | Instructor Guide

CTS Cohort 6 | CTS Day 16 | 2026-07-30 | 10:00 AM-3:00 PM | 6 students

Final Practical, Handoff, and RCS Closeout

Core rule: A professional does not guess. A professional checks, protects, and verifies.

Big idea: Competence is the ability to perform safely, explain decisions, verify results, and leave trustworthy evidence for the next person.

Architecture of the day

Time	Instructor move
10:00-10:20	Assessment briefing, PPE, and station boundaries
10:20-10:50	Final written knowledge check
10:50-12:30	Measurement, systems, and troubleshooting stations
12:30-1:00	Lunch and controlled reset
1:00-1:40	Final capstone wall QC
1:40-2:10	Evidence index and handoff preparation
2:10-2:40	Two-minute handoffs and instructor conferences
2:40-3:00	Reflection, next step, and final reset

Learning targets

- Complete the final written knowledge check
- Demonstrate measurement, inspection, and troubleshooting skills
- Present the capstone wall and evidence package
- Complete reflection and next-step planning

Materials and setup

- Six written assessments, scoring keys, practical rubrics, and clipboards
- Measurement/layout, systems-ID, isolated troubleshooting, and wall-QC stations
- Instructor-controlled fault inserts and station reset materials
- Six capstone walls with student evidence indexes
- Two-minute handoff rubric, timer, and conference notes
- PPE, boundary signage, reflection forms, and final-reset checklist

Instructor talking points

- Set a calm assessment frame: the goal is valid evidence, not trick questions.
- Review the station boundaries and how students request clarification without receiving answers.
- Explain the capstone rubric: safety, accuracy, system understanding, quality, verification, documentation, and handoff.
- Model a concise professional presentation.
- Close the RCS sequence by connecting strengths and next steps to apprenticeship habits.

Whiteboard plan

1. Safety first
2. Written check
3. Practical stations
4. Capstone handoff
5. Evidence upload
6. Reflection and closeout

Lab facilitation

Students rotate through measurement/layout, system identification, de-energized troubleshooting, and capstone inspection stations, then deliver a two-minute wall handoff using their evidence package.

Lab sequence

7. Assessment briefing
8. PPE/station check
9. Written assessment
10. Measurement station
11. Framing/system ID station
12. De-energized electrical troubleshooting station
13. Capstone QC
14. Evidence index
15. Two-minute handoff
16. Instructor conference
17. Reflection
18. Final reset

Safety boundaries

- All established RCS tool and energy boundaries remain active
- No speed bonus and no penalty for a justified stop-work call

- Instructor controls station reset and fault insertion
- Students disclose uncertainty rather than guess
- No field-work authorization is implied by completion

Evidence targets

- Final written assessment
- Practical station rubric
- Final wall QC
- Capstone photo/evidence index
- Two-minute handoff rubric
- Individual reflection

Quiz answer key

1. What is the core RCS professional rule? A professional does not guess. A professional checks, protects, and verifies.

2. How is wall square checked? Compare diagonal measurements and verify dimensions.

3. What must happen before continuity testing? The circuit must be de-energized and isolated.

4. Name the required capstone electrical devices. Two outlets, one switch, and one light point.

5. Why complete a pre-cover inspection? To verify hidden work before drywall conceals it.

6. What is the purpose of a punch list? To document and close incomplete, defective, or unverified work.

7. What completes troubleshooting? Correction, retest, documentation, and approval.

8. What should a professional handoff include? Scope, key decisions, verified results, evidence, and unresolved items.

9. Does course completion authorize unlicensed field electrical or plumbing work? No.

10. What should a student do when unsure during practical work? Stop, protect the work area, verify what is known, and ask for appropriate clarification.

Exit-ticket look-fors

- The RCS skill I am proudest of
- Evidence that supports that claim
- A skill I will keep practicing
- My next professional step

Google Classroom post

RCS Day 8 - Final Practical, Handoff, and RCS Closeout

Today students completed the RCS written check, practical stations, final wall QC, evidence index, two-minute handoff, and individual reflection. Submit the final evidence package and reflection before closeout.

Source and safety references

- **Canonical RCS skeleton:** /CANONICAL/00_INBOX/Downloads/rcs_curriculum_plan.md
- **Cohort 6 RCS01 source:** /CANONICAL/02_PROJECTS/CTS_Cohort_06/03_DAILY/D09_RCS01_2026-07-20/Source/lesson.md
- **OSHA PPE:** https://www.osha.gov/personal-protective-equipment/construction
- **OSHA eye and face protection:** https://www.osha.gov/laws-regs/regulations/standardnumber/1926/1926.102
- **OSHA circuit lockout/tagging:** https://www.osha.gov/laws-regs/regulations/standardnumber/1926/1926.417
- **Oregon electrical codes:** https://www.oregon.gov/bcd/codes-stand/pages/electrical.aspx
- **Oregon permits:** https://www.oregon.gov/bcd/lbdd/pages/oregon-permits.aspx

RCS08 | Morning Quiz - Answer Key

CTS Cohort 6 | CTS Day 16 | 2026-07-30 | 10:00 AM-3:00 PM | 6 students

Final Practical, Handoff, and RCS Closeout

1. What is the core RCS professional rule?

A professional does not guess. A professional checks, protects, and verifies.

2. How is wall square checked?

Compare diagonal measurements and verify dimensions.

3. What must happen before continuity testing?

The circuit must be de-energized and isolated.

4. Name the required capstone electrical devices.

Two outlets, one switch, and one light point.

5. Why complete a pre-cover inspection?

To verify hidden work before drywall conceals it.

6. What is the purpose of a punch list?

To document and close incomplete, defective, or unverified work.

7. What completes troubleshooting?

Correction, retest, documentation, and approval.

8. What should a professional handoff include?

Scope, key decisions, verified results, evidence, and unresolved items.

9. Does course completion authorize unlicensed field electrical or plumbing work?

No.

10. What should a student do when unsure during practical work?

Stop, protect the work area, verify what is known, and ask for appropriate clarification.

Scoring guidance

One point per item. Accept technically equivalent wording. Use errors to reteach before lab release. Safety-boundary errors must be corrected explicitly before the student begins the related task.

RCS08 | Student Packet

CTS Cohort 6 | CTS Day 16 | 2026-07-30 | 10:00 AM-3:00 PM | 6 students

Final Practical, Handoff, and RCS Closeout

Core rule: A professional does not guess. A professional checks, protects, and verifies.

Big idea: Competence is the ability to perform safely, explain decisions, verify results, and leave trustworthy evidence for the next person.

Learning targets

- Complete the final written knowledge check
- Demonstrate measurement, inspection, and troubleshooting skills
- Present the capstone wall and evidence package
- Complete reflection and next-step planning

Today's run

10:00-10:20 | Assessment briefing, PPE, and station boundaries

10:20-10:50 | Final written knowledge check

10:50-12:30 | Measurement, systems, and troubleshooting stations

12:30-1:00 | Lunch and controlled reset

1:00-1:40 | Final capstone wall QC

1:40-2:10 | Evidence index and handoff preparation

2:10-2:40 | Two-minute handoffs and instructor conferences

2:40-3:00 | Reflection, next step, and final reset

Key words

competency | practical assessment | acceptance criteria | verification | handoff | portfolio evidence | reflection | next step | professionalism | closeout

Guided worksheet

1. Final capstone self-assessment

_____

_____

2. Evidence index

_____

_____

3. One skill I can demonstrate independently

_____

_____

4. One skill requiring supervision

_____

_____

5. One next training or career action

_____

_____

Afternoon lab mission

Students rotate through measurement/layout, system identification, de-energized troubleshooting, and capstone inspection stations, then deliver a two-minute wall handoff using their evidence package.

Safety boundary

- All established RCS tool and energy boundaries remain active
- No speed bonus and no penalty for a justified stop-work call
- Instructor controls station reset and fault insertion
- Students disclose uncertainty rather than guess
- No field-work authorization is implied by completion

Build / test sequence

[ ] Assessment briefing

[ ] PPE/station check

[ ] Written assessment

[ ] Measurement station

[ ] Framing/system ID station

[ ] De-energized electrical troubleshooting station

[ ] Capstone QC

[ ] Evidence index

[ ] Two-minute handoff

[ ] Instructor conference

[ ] Reflection

[ ] Final reset

Evidence record

[ ] Final written assessment: _____

[ ] Practical station rubric: _____

[ ] Final wall QC: _____

[ ] Capstone photo/evidence index: _____

[ ] Two-minute handoff rubric: _____

[ ] Individual reflection: _____

Reflection and exit ticket

The RCS skill I am proudest of

_____

_____

Evidence that supports that claim

_____

_____

A skill I will keep practicing

_____

_____

My next professional step

_____

_____

Instructor verification

Status: [ ] Approved [ ] Correct and recheck [ ] Needs follow-up

Instructor initials: _____ Date/time: _____

RCS08 | Morning Quiz

CTS Cohort 6 | CTS Day 16 | 2026-07-30 | 10:00 AM-3:00 PM | 6 students

Final Practical, Handoff, and RCS Closeout

Name: _____ Date: _____

Answer from your own understanding. This is a teaching check, not a trap.

1. What is the core RCS professional rule?

_____

_____

2. How is wall square checked?

_____

_____

3. What must happen before continuity testing?

_____

_____

4. Name the required capstone electrical devices.

_____

_____

5. Why complete a pre-cover inspection?

_____

_____

6. What is the purpose of a punch list?

_____

_____

7. What completes troubleshooting?

_____

_____

8. What should a professional handoff include?

_____

_____

9. Does course completion authorize unlicensed field electrical or plumbing work?

_____

_____

10. What should a student do when unsure during practical work?

_____

_____