PV102 Day 1 Morning Quiz: Answer Key

Scoring notes and instructional rationales

10 points	Suggested: 8 ready	Use for review

Morning Quiz - Answer Key | Audience: Instructor | Monday, August 3, 2026

Item	Answer	Rationale / look-for
1	B. DC	PV modules produce direct-current electrical output.
2	A. Voltage	In a series connection, matching module voltages add while current is limited by the string.
3	B. Current	In a parallel connection, matching string currents add while voltage remains at the branch voltage.
4	C. Battery to controller	For the training hardware used in PV101, students followed the controller manufacturer's battery-first startup sequence. Always use the actual manufacturer's procedure.
5	B. Limit damaging current	A fuse or breaker opens the circuit when current exceeds its intended limit; it does not create or store energy.
6	B. De-energized and verified	Continuity and resistance checks require an electrically safe, de-energized circuit.
7	24 W	P = V x I = 12 V x 2 A = 24 W.
8	Any two: scope/work completed; verified measurements or results; condition/status; unresolved items; safety boundaries; next action.	A professional handoff separates what is complete and verified from what remains open.
9	Stop work, protect the area, verify the condition with the correct procedure/tool, and ask the instructor or qualified person.	Uncertainty is a stop condition, not permission to guess.
10	Accept any accurate statement: component ratings, functions, environment, compatibility, or client goals may not match the specific system.	PV102 shifts from identifying parts to matching a whole architecture to a real job.

Use the review diagnostically

- If items 2-3 are weak, review series and parallel behavior before Day 3 module analysis.
- If items 4-6 or 9 are weak, reinforce de-energization, manufacturer sequence, protection, and stop-work expectations before any later hands-on activity.
- If item 8 is weak, use the RCS handoff pattern: scope, verified evidence, unresolved items, next action.
- Do not treat this quiz as evidence that a student is qualified for live electrical work.