PV102 Day 8 Student Packet

Commissioning Troubleshooting and Professional Handoff

PV102 | CTS Day 24 | Student Print Packet
Test, document, and hand off what the system actually does. | Thursday, August 13, 2026

Today's rule

Test, document, and hand off what the system actually does.

Learning targets

- Use a commissioning sequence to verify before energizing.
- Interpret basic test results without guessing beyond evidence.
- Troubleshoot from symptom to boundary to measurement.
- Prepare a concise handoff that names what passed, what failed, what changed, and what remains unknown.

Morning quiz

1. Commissioning means:

- A. Verifying a system before/while placing it into service
- B. Buying the biggest inverter
- C. Painting a roof
- D. Guessing until it works

2. Before continuity testing, the circuit must be:

- A. De-energized and verified
- B. Fully energized
- C. Connected to utility
- D. Under maximum load

3. Polarity checks help prevent:

- A. Reverse connection damage or unsafe operation
- B. Too much sunlight
- C. Roof leaks only
- D. Bad handwriting

4. A professional handoff should include:

- A. Results, changes, unknowns, and next actions
- B. Only “it works”
- C. No measurements
- D. Guesswork

5. Good troubleshooting starts by:

- A. Defining the symptom and boundary
- B. Replacing random parts
- C. Blaming the battery immediately
- D. Skipping measurements

6. A 12 V battery reads 0 V at the load terminals. Name one possible boundary to check.

_____

_____

7. Why should failed tests be documented instead of hidden?

_____

_____

8. What should happen if a measurement does not make sense?

_____

_____

9. Name one item that belongs in a final PV102 handoff package.

_____

_____

10. Write the Day 8 rule in your own words.

_____

_____

Reference: decision order

Step	Action	Proof question
1	Define the job	What must the system accomplish?
2	Collect evidence	What is measured, observed, or still unknown?
3	Choose boundary	What must be protected, isolated, sized, or verified?
4	Defend the choice	What evidence supports the decision?
5	Handoff	What should the next person know?

Commissioning and Fault Handoff Challenge

Teams inspect a training system or fault card set, run a commissioning sequence, identify one fault, and deliver a final technical handoff.

Scenario options

- Training kit has a hidden open fuse and incomplete label.
- Paper system has reversed polarity at one component card and missing OCPD label.
- Mock client handoff has incomplete load table and no record of final voltage checks.

Team procedure

- Review the system scope and safety boundary.
- Complete pre-energization inspection using the checklist.
- Run only authorized de-energized checks first.
- Use evidence to identify the fault or missing documentation.
- Record pass/fail results and corrective action recommendation.
- Deliver a three-minute final handoff: system job, path, checks, fault, fix/next action, unknowns.

Team worksheet

Prompt	Team response
System/job statement	
Evidence used	
Decision made	
Safety boundary	
Top unknowns	
Next action	

Exit ticket

What is one thing you now refuse to accept as “good enough” without evidence?

_____

_____