RCS07 | Student Packet

CTS Cohort 6 | CTS Day 15 | 2026-07-29 | 10:00 AM-3:00 PM | 6 students

Integrated Wall Build: Correct, Complete, Prove

Core rule: A professional does not guess. A professional checks, protects, and verifies.

Big idea: Integration means every system fits, remains inspectable, and can be explained with evidence - not merely that the wall looks finished.

Learning targets

- Complete remaining capstone framing, electrical, and drywall work
- Run a subsystem and whole-wall QC inspection
- Diagnose and correct one documented defect
- Prepare a professional handoff package

Today's run

10:00-10:15 | Arrival, PPE, retrieval warm-up

10:15-10:30 | Morning quiz

10:30-10:50 | Quiz review and whole-wall QC frame

10:50-11:20 | Subsystem and whole-wall inspection model

11:20-12:00 | Punch-list and acceptance-criteria practice

12:00-12:30 | Handoff evidence model and rework release

12:30-1:00 | Lunch and controlled reset

1:00-2:25 | Approved rework and capstone completion lab

2:25-2:45 | Retest, whole-wall QC, handoff practice, cleanup

2:45-3:00 | Exit ticket and final-practical preview

Key words

integration | punch list | quality control | nonconformance | rework | handoff | evidence | acceptance criteria | traceability | reset

Guided worksheet

1. Complete the whole-wall QC checklist.

_____

_____

2. Create a numbered punch list.

_____

_____

3. Record one defect and its evidence.

_____

_____

4. Record the correction and retest.

_____

_____

5. Draft a 60-second handoff explanation.

_____

_____

Afternoon lab mission

Students complete their individual capstone walls, inspect framing dimensions, window opening, two outlets, switch/light path, drywall fit, fasteners, labeling, and evidence. Each student corrects at least one documented punch-list item and prepares a handoff.

Safety boundary

- Reapply the specific tool and energy controls for each task
- No energized student work
- Instructor approval before reopening covered or terminated systems
- Keep rework zones isolated
- Stop when a correction would create a new hazard or exceed training scope

Build / test sequence

[ ] Pre-task plan

[ ] Energy-state verification

[ ] Whole-wall baseline inspection

[ ] Create punch list

[ ] Prioritize safety/functional defects

[ ] Complete approved work

[ ] Subsystem QC

[ ] Whole-wall QC

[ ] Correct one documented issue

[ ] Retest/reinspect

[ ] Capture evidence

[ ] Practice handoff

[ ] Reset

Evidence record

[ ] Pre-task plan: _____

[ ] Whole-wall QC checklist: _____

[ ] Punch list: _____

[ ] Before/correction/after evidence set: _____

[ ] Draft handoff: _____

Reflection and exit ticket

Name your highest-priority punch item

_____

_____

Describe the correction

_____

_____

State the retest evidence

_____

_____

Name any unresolved item honestly

_____

_____

Instructor verification

Status: [ ] Approved [ ] Correct and recheck [ ] Needs follow-up

Instructor initials: _____ Date/time: _____

RCS07 | Morning Quiz

CTS Cohort 6 | CTS Day 15 | 2026-07-29 | 10:00 AM-3:00 PM | 6 students

Integrated Wall Build: Correct, Complete, Prove

Name: _____ Date: _____

Answer from your own understanding. This is a teaching check, not a trap.

1. What is a punch list?

_____

_____

2. What should a useful punch item include?

_____

_____

3. What is rework?

_____

_____

4. What is traceability?

_____

_____

5. Why inspect subsystems before the whole wall?

_____

_____

6. What energy rule remains active during correction?

_____

_____

7. What four photo types support strong evidence?

_____

_____

8. Should unresolved items be hidden during handoff?

_____

_____

9. What proves a correction worked?

_____

_____

10. When is a wall ready for handoff?

_____

_____