RCS06 | Morning Quiz - Answer Key

CTS Cohort 6 | CTS Day 14 | 2026-07-28 | 10:00 AM-3:00 PM | 6 students

Drywall Installation and Finish Readiness

1. Why inspect before covering the wall?

Hidden framing and rough-in problems become harder to verify or correct after cover.

2. What is score and snap?

Cutting the face paper, snapping the gypsum core, then cutting the back paper.

3. What is an overdriven fastener?

A fastener that breaks the face paper and loses proper holding quality.

4. Why measure an opening from two reference edges?

To locate it accurately and reduce transfer error.

5. What must protect workers during dusty tasks?

The task's engineering controls, housekeeping, ventilation, and required PPE/SDS procedures.

6. May drywall cover an unapproved rough-in?

No.

7. What should a correct fastener do?

Create a slight dimple without tearing the face paper.

8. Why dry-fit before fastening?

To verify dimensions, openings, and edge support before committing.

9. What is finish readiness?

The board is secure, joints/openings are sound, fasteners are correct, and the surface is ready for the next finishing step.

10. What professional habit applies to cutouts?

Measure, mark, verify, then cut.

Scoring guidance

One point per item. Accept technically equivalent wording. Use errors to reteach before lab release. Safety-boundary errors must be corrected explicitly before the student begins the related task.